

CA522/2



connectwell
THE RIGHT CONNECTION

Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the centre of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, 10 or 100 pole assemblies and are ready for immediate installation.

PRODUCT SPECIFICATION

Rated Current	32 A
Torque	0.4 Nm

ORDERING INFORMATION

CAT. NO.	DESCRIPTION	STD. PACK
CA522/2	Pre assembled Shorting Link for 2 way shorting.	100
CA522/3	Pre assembled Shorting Link for 3 way shorting.	100
CA522/4	Pre assembled Shorting Link for 4 way shorting.	100
CA522/10	Pre assembled Shorting Link for 10 way shorting.	10

SUITABLE FOR

CTS2.5	4 sq.mm Standard Feed Through Terminal Blocks
CTS4SC	4 sq.mm Spring Loaded Feed Through Terminal Blocks