## CA725/2





## Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the center of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, 10 or 100 pole assemblies and are ready for immediate installation.

PRODUCT SPECIFICATION		
Rated Current	101 A	
Torque	0.8 Nm	

ORDERING INFORMATION			
CAT. NO.	DESCRIPTION	STD. PACK	
CA725/2	Pre assembled Shorting Link for 2 way shorting	50	
CA725/3	Pre assembled Shorting Link for 3 way shorting	20	
CA725/4	Pre assembled Shorting Link for 4 way shorting	20	
CA725/10	Pre assembled Shorting Link for 10 way shorting	10	

SUITABLE FOR	
CTS25UN	25 sq.mm Standard Feed Through Terminal Blocks
CTS25UN	25 sq.mm Standard Feed Through Terminal Blocks