

CA728/2



Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the center of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, 10 or 100 pole assemblies and are ready for immediate installation.

PRODUCT SPECIFICATION

Rated Current	41 A
Torque	0.8 Nm

ORDERING INFORMATION

CAT. NO.	DESCRIPTION	STD. PACK
CA728/2	Pre Assembled Shorting Link Assemblies with 2 poles	100
CA728/3	Pre Assembled Shorting Link Assemblies with 3 poles	100
CA728/4	Pre Assembled Shorting Link Assemblies with 4 poles	100
CA728/10	Pre Assembled Shorting Link Assemblies with 10 poles	10

SUITABLE FOR

CSB3/N3USH	M3 sized Stud Type Hinge Terminal Blocks, suitable for operation with screwdriver and nut driver.
CSB3/N3UL	M3 sized Stud Type Terminal Blocks, suitable for operation with screwdriver and nut driver.
CBS3U	M3 sized Stud Type Terminal Blocks, suitable for operation with screwdriver.
CSB3/N3U	M3 sized Stud Type Terminal Blocks, suitable for operation with screwdriver and nut driver.