

CA741/2

**connectwell**
THE RIGHT CONNECTION

Insulated Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the centre of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, 10 or 100 pole assemblies and are ready for immediate installation. Insulated Preassembled internal Shorting link assemblies provide shock protection when installed on Terminal Blocks.

PRODUCT SPECIFICATION

Rated Current	24 A
Torque	0.4 Nm

ORDERING INFORMATION

CAT. NO.	DESCRIPTION	STD. PACK
CA741/2	Insulated Pre assembled Shorting Link for 2 way shorting	100
CA741/3	Insulated Pre assembled Shorting Link for 3 way shorting	100
CA741/4	Insulated Pre assembled Shorting Link for 4 way shorting	100
CA741/10	Insulated Pre assembled Shorting Link for 10 way shorting	10
CA741/100	Insulated Pre assembled Shorting Link for 100 way shorting	10

SUITABLE FOR

CTS2.5UN	2.5 sq.mm, 5 mm thick Feed Through Terminal Block
----------	---------------------------------------------------