

CA743/2



connectwell
THE RIGHT CONNECTION

Insulated Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the centre of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, 10 pole assemblies and are ready for immediate installation. Insulated pre assembled shorting link assemblies provide shock protection when installed on Terminal Blocks.

PRODUCT SPECIFICATION

Rated Current	41 A
Torque	0.5 Nm

PRODUCT DIAGRAM

Hello, world!

ORDERING INFORMATION

CAT. NO.	DESCRIPTION	STD. PACK
CA743/2	Insulated Pre assembled Shorting Link for 2 way shorting	100
CA743/3	Insulated Pre assembled Shorting Link for 3 way shorting	50
CA743/4	Insulated Pre assembled Shorting Link for 4 way shorting	50
CA743/5	Insulated Pre assembled Shorting Link for 5 way shorting	50
CA743/6	Insulated Pre assembled Shorting Link for 6 way shorting	10
CA743/7	Insulated Pre assembled Shorting Link for 7 way shorting	10
CA743/10	Insulated Pre assembled Shorting Link for 10 way shorting	10

SUITABLE FOR

CTS6SC	6 sq.mm Spring Loaded Feed through Terminal Blocks
CTS6U	6 sq.mm Standard Feed Through Terminal Blocks
CTS6	6 sq.mm Standard Feed Through Terminal Blocks